



**PUBLIC WORKS DEPARTMENT**

115 W COURT STREET, MAIL STOP, 303, GOLDENDALE, WASHINGTON 98620 • FAX 509 773-5713 • VOICE 509 773-4616  
JEFF HUNTER. - PUBLIC WORKS DIRECTOR

**INFORMATIONAL COMMUNICATION NO.2**

**TO:** Prospective Bidders

**PROJECT:** Goldendale Fuel Facility

**BID OPENING DATE:** March 24, 2026

The following questions were received by Klickitat County Public Works from prospective bidders and the responses are the following:

**Question #1: is bid item 25 – erosion control intended to cover hydroseeding??**

Answer #1: yes, item 25 – erosion control is intended to cover hydroseeding for all disturbed areas not covered by a solid surface.

**Question #2: are items 26 and 27 have a quantity of 1 L.F., will the county pay for the actual length installed as measured in the field?**

Answer #2: Yes, the County will pay for the actual L.F. installed for items 26 and 27.

**Question #3: does the county have a preferred fuel distribution equipment supplier/installer?**

Answer #3: No, the County does not.

**Question #4: The specs state 120 days for project completion, when will the 120 days start?**

Answer #4: The working days will begin when the NTP is issued, but can be halted due weather and/or long lead items.

**Question #5: Is there a scheduled site walkthrough?**

Answer: No, but contact Rick at 509-250-1300 for a site visit.

**Question #6: Does this project have any BABAA requirements?**

Answer #6: No BABAA requirements.

**Question #7: Clarify the anticipated function of the Veeder Root Control Software System?**

Answer #7: refer to the revised sheet M0.2 that is in Addendum #1, posted on 3/17/2026.

**Question #8: The specs call out UL-142 but the drawings indicate UL-2085, confirm that UL-2085 tanks are required.**

Answer#8: UL-2085 tanks are required.

**Question #9: Eagle tanks are specified in the drawings; can other tanks be substituted?**

Answer #9: Alternate UL-2085 tanks are accepted upon approval.

**Question #10: Please confirm that ORVR has been approved and that stage II Vapor Recovery is not required?**

Answer #10: Stage II Vapor Recovery is not required if vehicles have ORVR.

**Question #11: Clarify if a fuel management system is part of the bid scope?**

Answer #11: Refer to the updated sheets in Addendum #1 posted on 3/17/26. Mechanical sheets M0.2 and M2.1 for fuel management system, Electrical sheets E1.1, E1.3, E1.4, and E1.5 have been updated to reflect dispensers and controls.

**Question #12: Gas Boy dispensers are specified in the drawings; can other dispensers be substituted?**

Answer #12: Alternate dispensers are accepted upon approval.



---

Rick Milliren  
Deputy Director of Facilities  
Phone – 509.773.2375  
Cell – 509.250.1300  
Email – rickm@klickitatcounty.org